



# SEVA SADAN'S COLLEGE OF EDUCATION

Ulhasnagar – 421 003

NAAC – 3<sup>rd</sup> Cycle Grade 'A'

Affiliated to University of Mumbai

Website :- [www.sscoe.edu.in](http://www.sscoe.edu.in)

Contact No.0251-2712065.

Dr. Renuka K. Shewkani

I/c. Principal

B.Sc., M.A., M.Ed., SET, Ph.D.

Date: 11<sup>th</sup> July, 2023

**Subject: Quotation Notice for Construction of Class Room in Seva Sadan's College of Education, Ulhasnagar -3**

Dear Sir/Madam,

The Seva Sadan's College of Education, Ulhasnagar invites sealed quotations from eligible and experienced contractors for the execution of civil works on the college premises. The detailed scope of work and specifications are as follows:

**Project Details:**

- **Project Name:** Construction of Class Room in Seva Sadan's College of Education, Ulhasnagar -3.

**Project Scope:**

Sr.No.	Item Description	Quantity	Units
	<b>CLASSROOM</b>		
1	Dismantling Loose Plaster wall tiles, flooring, and other unwanted Items and stacking, re useable items, in Ground Floor Compound School.	3840	Sq.ft.
2	Repairs to RCC Damaged Members such as slab, beam, columns by using Readymix Polymer Modified Mortar (uptp 20 mm thick). Removing loose rust from the reinforcement bars by wire brushing, light hammering etc. and applying sulphate and chloride free inorganic single component rust remover (RUSTICIDE- UNANDA MAKE) conforming to IS 9077. The rusted surface shall become blackish non rusted colour. After 24 hours of application of rust remover, loose particles	415	Sq.ft.

	shall be removed by brush. Applying bonding coat slurry of high performance acrylic polymer POLYALK EP of Sunanda make or equivalent over Ready mix polymer modified mortar. Mix 1 Kg. polyalk EP with 0.5 kg. of cement. Finish with ready to use repair polymer modified mortar.		
3	<b>Cement Plaster (Internal):</b> Providing & applying cement - sand plaster (12mm average thickness) for internal walls in plumb & true surface & curing for 7 days (2 times a day).	3580	Sq.ft.
4	providing and constructing 9" thick brick masonry with conventional / IS type bricks in cement mortar 1:4 of inner wall including bailing out water manually, striking joints on exposed faces & watering etc.	1335	Sq.ft.
5	Debris Carrying away outside the compound of shool.	8	Nos.

3. **Site Location:** Seva Sadan's College of Education, Seva Sadan Marg, Opp. Central Hospital, Ulhasnagar-421 003 Dist: Thane

4. **Timeline:** within a month from date of issue of work order

Interested contractors are requested to submit their quotations in sealed envelopes marked "Quotation for Construction of Class Room in Seva Sadan's College of Education, Ulhasnagar -3 on or before 01<sup>st</sup> August, 2023, 5.00 p.m. at the following address:

**Seva Sadan's College of Education  
Seva Sadan Marg, Opp. Central Hospital,  
Ulhasnagar-421 003**

The quotation should include the following information:

1. Detailed breakdown of costs, including materials, labor, and any other relevant expenses.
  2. Validity period of the quotation.
  3. Any terms and conditions related to the quotation.
  4. Company profile, including past experience in similar projects.
- The college reserves the right to accept or reject any or all quotations without assigning any reason thereof. The decision of the college will be final and binding.
  - For any clarifications or inquiries, interested contractors can contact Administration Office of Seva Sadan's College of Education

**By Order,  
Seva Sadan's College of Education**